



GENERAL NOTES

If not indicated on this plan, north point must be confirmed prior to installation to ensure that slides do not face due south.

No allowance has been made for soft landscaping (trees, mounds, planting, turf or general reinstatement). These should be carried out by others.

Exact positions & orientation of new items may be subject to a final site survey and setting out plan.

Any inconsistencies on site should be verified with HAGS before commencement of work.

HAGS recommend that existing trees are risk-assessed by the client to ensure the integrity of accessible branches, that overhanging limbs do not conflict with new play equipment or vehicle access and that the canopy will not produce excessive leaf drop which could cause a hazard within the play area.

This design layout conforms to the relevant EN Safety Standard.

KEY

- Falling Space Zone (EN1176)
- Free Space Zone (EN1176)
- Clearance Zone (EN1176)
- Wet Pour into grass at a 45° angle, by an additional 300mm and depth of 300mm
- Addendum - Optional Wildflower Planting

Key	Description	FHF	Surfacing
1	Special UniMini Multi-Unit	1.3m	Supply and lay 173m ² total of colour/fleck flush wet pour [as per design] Breakdown: 147m ² @ 40mm depth 26m ² @ 50mm depth
2	Anky Springer with backrest	0.6m	
3	Turtle 4-Way Springer	0.6m	
4	Mira 2.4m Swing with Tango 2-user Seat + Cradle Seat	1.4m	
5	Lille Swing with Dolly Nest Seat	0.9m	
6	Swirl Whirl Spinner	0.55m	Supply and install 173m ² of 100mm MOT type 1 Supply and install 173m ² of geotextile membrane Supply and install 12m of PCC edging
7	Crater Round Trampoline	1m	Wet Pour into grass at a 45° angle, by an additional 300mm and depth of 300mm to manage 'shrinkage' of the wet pour over time.
8	Animal Spelling Play Panel + Posts	n/a	grass (position to be discussed)
9	Tile Slide Snake Play Panel + Posts	n/a	grass (position to be discussed)
10	Balance Beam	0.6m	grass
11	Rope Walk	0.5m	grass
12	Inclined Balance Beam	0.6m	grass
13	Ross Ice Shelf Stepping Stones (to be split up)	<0.6m	grass
14	3no Rubber Mushrooms	<0.6m	grass (position to be discussed)
15	Forest Saver Picnic Table	n/a	new Tarmac pad
16	Evergreen Seat	n/a	new Tarmac pad
17	Beau 42 litre Litter Bin	n/a	grass
18	Rainbow Thermoplastic Graphic	n/a	new Tarmac pad
19	Frog Hopscotch Thermoplastic Graphic	n/a	existing Tarmac

16m² for 4m x 4m Tarmac Pad.
6m² for 2no 3m x 2m Tarmac Pads under Picnic Tables, including Tree Root Barriers
Tarmac Spec: Supply and lay 22m² of 60mm depth of 20mm dense base course and 40mm depth of 6mm wearing course.
Supply and lay blinding sand across the whole of the tarmac areas, maintaining 1:60 crossfall.
Soft dig excavation to 250mm & cart away spoil - 22m²
Supply and install 22m² of 150mm MOT type 1, maintaining 1:60 crossfall.
Supply and install 30m² of geotextile membrane, allowing a 300mm overlap jointing.
Supply and install 30m of 915 x 150 x 50 PCC edging: 4m x 4m pad = 16 Lm + Picnic Table pads = 7 Lm x 2 = 14 Lm

CUSTOMER
Reading Borough Council

PROJECT
Blagrave Road
Recreation Ground

TITLE
Toddler Area



T: 0845 260 1655
E: sales@hags.co.uk
W: www.hags.co.uk

HAGS - South
Clockhouse Nurseries
Clockhouse Lane East
Egham, Surrey
TW20 8PG
United Kingdom

DATE: 11/12/20 SCALE: 1:00 @ A2
DRAWN BY: G.H. CHECKED BY: N.B.

DRAWING NUMBER: Q-26646-Y2R4-C REVISION: 0

© HAGS 2020 SHEET 1 OF 1

Re Trampoline - Please note:
Drainage works not included as standard.
Consideration should be given to possible water retention through a high-water table / non-free draining soil, which can only be determined at point of excavation and installation.
HAGS can provide optional drainage costs which may / may not be required upon request