

Blaggrave Road Recreation Ground Reading Borough Council

Quote No. 4801577

Dwn BF Scale 1:250@A2 16.12.2020

Do not scale from this drawing

design
make
play
SutcliffePlay



No.	Code	Description
01	DZM451	Toddlerzone+ Dardfoll
02	SSB150	Flower Springle
03	SSB160	Ladybird Springle
04	SWC0622	1.8m High Swing with 2 x Cradle Seats
05	PZW6857BA	Climber For All (Trut Fruit)
06	CZM224TBA	Mission Ultimatum (Blue)
07	SWD450	Wipe Out
08	SMB230401	Large Trampoline
09	SMB260	Enrol Discus
10	COBR001	Coara Swing
11	SWD170	Back to Back Roundabout
12	MTUD23	Mountain Hop & Shop
13	FSEED01	Flower Explorer Play Panel
14	FSEED01	Spider's Web Explorer Play Panel
15	SWD150	Curticle
16	MTUD10	Sansory Flower
17	620385	Surrey Forest-Saver Picnic Table (X2)
18	3111	Evergreen Seat
19	221	Beau Litter Bin (X2)
20	HO1-031	Jump Leaves with Numbers 1-8
21	HO1-011	Clock Graphic
22	D01-008	Ladybird Graphic
23	D01-013	Bee Graphic
24	SN1-003	3D Ladybird

All furniture locations to be confirmed by client

Excavate base - area 492.5m²
 Install new wet pour - total area 492.5m²
 <1m H/C - 282m²
 1m H/C - 46.2m²
 1.2m H/C - 41.5m²
 1.5m H/C - 75.3m²
 1.8m H/C - 17.3m²
 2m H/C - 15.2m²
 2.4m H/C - 46m²
 2.8m H/C - 56.7m²
 Install new PCC edging - 1.71m
 Chase perimeter - 951m

Client to remove multi-play & swing
 Client to remove bark pit & edging

Install geotextile membrane - area 16.5m²
 Install new concrete - area 16.5m²
 Install new timber edging - 171m
 Remove bark pit - area 132m²
 Remove timber edge board - 51.53m
 Excavate base - area 174m²
 Install new 40mm wet pour - area 174m²
 Chase perimeter - 481m
 Carefully remove 4 x swing barriers - 8 legs
 Remove seesaw - 2 legs
 Remove springle - 1 leg
 Remove savings 4 legs (4lg)
 Remove multi-play - 7 legs (4 dig)
 Remove bench x 2 - 8 legs
 Remove picnic bench x 2 - 16 legs

Remove tarmac - area 14m²
 Regulate base - area 14m²
 Install new base - area 7.6m²
 Install new tarmac as per spec - 21.6m²
 Install new PCC edging - 13.51m

